



Department
for Environment
Food & Rural Affairs

Report on measures for 2014 exceedance of the Target Value for Benzo[a]pyrene in Yorkshire and Humberside non-agglomeration zone (UK0034)

November 2016



© Crown copyright 2016

You may re-use this information (excluding logos) free of charge in any format or medium, under the terms of the Open Government Licence v.3. To view this licence visit www.nationalarchives.gov.uk/doc/open-government-licence/version/3/ or email PSI@nationalarchives.gsi.gov.uk

This publication is available at www.gov.uk/government/publications

Any enquiries regarding this publication should be sent to us at

Air Quality
Department for Environment, Food and Rural Affairs
Area 2C
Nobel House
Smith Square
London
SW1P 3JR

Email: air.quality@defra.gsi.gov.uk

With technical input from Ricardo Energy & Environment

www.gov.uk/defra

Contents

1. Introduction	4
1.1 Context.....	4
1.2 Status of zone	4
2 Exceedance situation Yorkshire and Humberside [B[a]P_UK0034_2014_1] related to industrial emissions	7
2.1 Description of exceedance	7
2.2 Source apportionment.....	10
2.3 Measures	14

1. Introduction

1.1 Context

Under the EU Directive 2004/107/EC¹, the target value (TV) for Benzo[a]pyrene (B[a]P) is an annual mean concentration of 1 nanogram (one billionth of a gram (10^{-9}) per cubic metre (m^{-3}) of ambient air or lower. The Directive requires that Members States report on measures in place to address the exceedance of the TV and that all reasonable measures that do not entail disproportionate cost should be taken to ensure this target is not exceeded.

Exceedance of the TV was reported in 2013 in the Yorkshire and Humberside non-agglomeration zone and a report on measures was published detailing the exceedance and the measures in place².

This document reports the exceedance situation for 2014 reflecting the more recent assessment and updating the 2013 report on measures.

1.2 Status of zone

This is the report on measures required for exceedances of the TV for B[a]P within the Yorkshire & Humberside zone identified within the 2014 UK air quality assessment. Exceedances within this zone were identified on the basis of measurement data with model results, on a 1 km x 1 km grid resolution, providing supplementary information. This exceedance was reported via e-Reporting dataflow G³ on attainment and Air Pollution in the UK⁴.

Table 1 summarises the spatial extent and associated resident population for the exceedances identified in this zone, as reported via e-Reporting.

¹ <http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=OJ:L:2005:023:0003:0016:EN:PDF>

² https://uk-air.defra.gov.uk/assets/documents/reports/bap-nickel-measures/bap_yorkshireandhumberside_UK0034_reportonmeasures_2013.pdf

³ <http://cdr.eionet.europa.eu/gb/eu/aqd>

⁴ <http://uk-air.defra.gov.uk/library/annualreport/index>



Table 1. Area exceeding B[a]P target value in 2014 and associated population for zone UK0034

Zone code	Zone Name	Area exceeding TV (km ²)	Population exceeding TV
UK0034	Yorkshire & Humberside	10	1805

Figure 1a shows the locations of the exceedances in the context of the zone as a whole. Figure 1b shows the part of the zone including the exceedances in more detail.

Figure 1. Location of exceedance of the B[a]P target value on 2013 in zone UK0034 Yorkshire & Humberside. Areas of the zone in exceeding grid squares are marked red.

a) The whole zone



b) The exceedance locations at higher spatial resolution



An initial source apportionment was carried out and this analysis identified one exceedance situation within this zone

- Yorkshire and Humberside [B[a]P_UK0034_2014_1] related to industrial emissions (area of exceedance 10 km²)

This following section details the exceedance situation in the zone including a description of the exceedance situation, maps, information on source apportionment and a list of measures already taken or to be taken. Information on measures is reported within e-Reporting dataflow K⁵.

An exceedance situation for B[a]P related to domestic combustion emissions was reported for this zone in 2013 at Castleford. As noted in the 2013 report on measures the inclusion of the existing smoke control area present in Castleford would likely remove this exceedance in future years. This was indeed the case and no exceedance in this location was reported in 2014.

⁵ <http://cdr.eionet.europa.eu/gb/eu/aqd>

2 Exceedance situation Yorkshire and Humberside [B[a]P_UK0034_2014_1] related to industrial emissions

2.1 Description of exceedance

This exceedance situation is an area of exceedance 10 km² to the north east of Scunthorpe in Lincolnshire. Figure 2 shows the location of the exceedance situation in detail. The exceeding grid squares are numbered in Figure 2 and in subsequent tables for easy reference. The resident population associated with this exceedance situation is 1,805, the majority (1,701) being in exceeding grid square 8, which is the exceedance square in the south west of the exceedance situation. It is highlighted with a white border in Figure 2 below. The remaining resident population of 98 is within exceeding grid square 4 at High Santon with a further 7 residents in grid square 6 at Dawes Lane. The remainder of the grid squares have no resident population and several are largely or wholly within the Longs Steel UK Ltd steelworks industrial complex area.

Table 2 lists the measured exceedances of the TV for B[a]P associated with this exceedance situation.


Table 2. Exceedances of the target for B[a]P in exceedance situation Yorkshire and Humberside [B[a]P_UK0034_2014_1]

Station (Eol code)	Annual mean concentration (ngm ⁻³) in 2014	Data capture (%)
Scunthorpe Low Santon (GB1004A)	3.6	92
Scunthorpe Town (GB0841A)	3.5	90

Figure 2 also shows the locations of the monitoring sites associated with the exceedance situation and the locations of the key industrial sources. The exceeding grid squares within this exceedance situation are numbered and the numbers correspond to those in subsequent tables. Grid squares 1, 3 and 7 have no resident population and are not part of the steelworks industrial complex area. Grid squares 4

and 8 are largely outside of the steelworks industrial complex area and have resident populations of 98 at High Santon and 1,701 at Frodingham respectively. Grid squares 2, 5 and 10 have no resident population and are wholly within the steelworks industrial complex area. Grid square 6 is largely within the steelworks industrial complex area and has a resident population of 7. Grid square 9 has no resident population and is largely within the steelworks industrial complex area.

Figure 2. Exceedance situation Yorkshire and Humberside [B[a]P_UK0034_2014_1]. Exceeding grid squares are marked red. Locations of coke works at Appleby and Dawes Lane and sinter plant at Scunthorpe are also shown as well as the two monitoring sites at Scunthorpe Town and Scunthorpe Low Santon.



2.2 Source apportionment

Table 3 provides a breakdown of the main emission sources (source apportionment) that have contributed to the grid squares in this exceedance situation, highlighting the significant contribution from industrial sources. The penultimate column is the total from all emission sources. The values in this column have been rounded to 1 decimal place for consistency with the values used in the compliance assessment. The values in the other columns have not been rounded. The other shaded columns are the subtotals for the regional, urban background and local contributions. Table 4 gives a more detailed source apportionment indicating how the separate industrial processes contribute to the total industrial figure. This shows that the coke ovens at Appleby and Dawes Lane are the main sources associated with this exceedance situation, with the relative proportions from these two sources varying for each grid square.

Table 3. Source apportionment for exceedance situation Yorkshire and Humberside [B[a]P_UK0034_2014_1]. Annual mean B[a]P concentration (ngm⁻³)

Grid square number	OS easting (m)	OS Northing (m)	Zone	a) Regional background: Total	b) Urban background increment: Total	Urban background increment: Traffic	Urban background increment: Industry	Urban background increment: commercial and	Urban background increment: Shipping	Urban background increment: Off road mobile	Urban background increment: Other	c) Local increment: Total	Local increment: Industry including heat and power	Total for all emission sources (a+b+c)	Resident population
1	493500	413500	34	n/a	0.140	0.002	0.014	0.053	0.000	0.002	0.069	1.179	1.179	1.3	0
2	491500	412500	34	n/a	0.112	0.002	0.018	0.040	0.000	0.004	0.048	1.504	1.504	1.6	0
3	492500	412500	34	n/a	0.131	0.002	0.016	0.047	0.000	0.003	0.063	3.887	3.887	4.0	0
4	493500	412500	34	n/a	0.135	0.002	0.015	0.049	0.000	0.002	0.067	1.773	1.773	1.9	98
5	491500	411500	34	n/a	0.113	0.002	0.022	0.039	0.000	0.005	0.045	4.103	4.103	4.2	0
6	492500	411500	34	n/a	0.101	0.002	0.015	0.037	0.000	0.003	0.044	4.107	4.107	4.2	7
7	493500	411500	34	n/a	0.128	0.002	0.014	0.044	0.000	0.002	0.065	1.192	1.192	1.3	0

Grid square number	OS easting (m)	OS Northing (m)	Zone	a) Regional background: Total	b) Urban background increment: Total	Urban background increment: Traffic	Urban background increment: Industry	Urban background increment: commercial and	Urban background increment: Shipping	Urban background increment: Off road mobile	Urban background increment: Other	c) Local increment: Total	Local increment: Industry including heat and power	Total for all emission sources (a+b+c)	Resident population
8	490500	410500	34	n/a	0.137	0.005	0.018	0.049	0.000	0.011	0.054	1.043	1.043	1.2	1701
9	491500	410500	34	n/a	0.112	0.003	0.018	0.041	0.000	0.004	0.045	2.733	2.733	2.8	0
10	492500	410500	34	n/a	0.101	0.002	0.014	0.037	0.000	0.003	0.045	1.066	1.066	1.2	0

Table 4. Detailed source apportionment for industrial sources only for exceedance situation Yorkshire and Humberside [B[a]P_UK0034_2014_1]. Annual mean B[a]P concentration (ngm⁻³)

Grid square number	OS easting (m)	OS Northing (m)	Zone	Appleby coke ovens	Dawes Lane coke ovens	Scunthorpe sinter plant	Local increment: Industry including heat and power production
1	493500	413500	34	0.411	0.718	0.050	1.179
2	491500	412500	34	0.537	0.946	0.022	1.504
3	492500	412500	34	0.866	2.969	0.052	3.887
4	493500	412500	34	0.736	0.979	0.058	1.773
5	491500	411500	34	2.580	1.506	0.017	4.103
6	492500	411500	34	2.451	1.591	0.064	4.107
7	493500	411500	34	0.664	0.476	0.052	1.192
8	490500	410500	34	0.710	0.327	0.006	1.043
9	491500	410500	34	2.258	0.475	0.000	2.733
10	492500	410500	34	0.783	0.263	0.020	1.066

A revised modelling methodology incorporating a finer spatial scale for dispersion modelling of all coke ovens in the UK and revision to the emissions rate for the coke ovens at Scunthorpe have been adopted for the 2015 compliance assessment for B[a]P that were not incorporated into 2014 reporting.

2.3 Measures

The main overview report contains more information on how industrial sites are regulated. There are no specific Best Available Techniques (BAT) conclusions designed to reduce B[a]P under the Industrial Emissions Directive (EU Directive 2010/75/EU). However, there are some narrative and specific BAT Conclusions to minimise particulate emissions, indirectly reducing B[a]P emissions. Permit conditions transposing these into the forthcoming IED permit will focus on the Coke Ovens and Sinter plant which are the main sources of this pollutant. BAT Reference Document (BREF)⁶ contains stringent requirements for iron and steel works to significantly reduce their fugitive emissions, including Polycyclic Aromatic Hydrocarbons (PAH) (B[a]P is a pollutant from this chemical group).

The coke ovens at Appleby and Dawes Lane are the main sources associated with the exceedance in this zone. The Environment Agency have conducted a review of the permit at the British Steel (formerly Longs Steel UK Ltd) installation. This was done against the BAT conclusions contained in the revised Steel and Iron BREF that was published in March 2012. In addition, the owners of the steelworks announced in October 2015 their intention to close down the coke ovens at Dawes Lane. Dawes Lane Coke Oven (DLCO) subsequently closed on the first compliance day for IED on the 8th March 2016.

During 2015, the performance of both coke ovens plants was poor at the then Tata Steel installation. Following pressures to improve, a strategic operational review concluded in Oct 2015 that alongside the closure of Dawes Lane Plant there would be a focused investment in the Appleby coke oven. The owners of the steelworks are currently working through a large project to decommission and close down Dawes Lane whilst Appleby Coke Oven is refurbished. As such the measures in the November 2015 report of measures for Dawes Lane Coke Oven can now be discounted.

Appleby Coke Oven (4 Batteries) has been further progressing their Coke Oven recovery project, both the Battery's and By-products plant. The Batteries have been running at well under 75% capacity with complete refurbishment of Battery 3 on hot idling (no coke production, heating on to maintain refractory) and on Battery 1, 2 and 4, some slot ovens out of service to prevent pollution and part of a two year intensive maintenance and improvement programme

⁶ http://eippcb.jrc.ec.europa.eu/reference/BREF/IS_Adopted_03_2012.pdf

The Environment Agency have set a permit condition in the 8 Feb 2016 issued EPR IED permit HP 3736AW to review and report on measures to prevent and minimise PAH emissions and the PAH AQ Management plan will be due in September 2016. A transitional report on measures has been received by the Environment Agency. As such the measures set out in the table to prevent and minimise PAH have been updated. A further update on the improvement conditions is expected to be available in February 2017

Table 5 sets out measures that are being taken or are to be taken, some of which are subject to the outcome of the review of the permit conditions or affected by the closure of the Dawes Lane coke ovens. Measures contained in the PAH Improvement Plan formally adopted by the steelworks in March 2013 and the transitional report on measures provided earlier this year are included.

Table 5. Table of measures taken or to be taken at Scunthorpe industrial site

Measure code	Description	Classification	Implementation dates	Other information		Comment	
1	Polycyclic Aromatic Hydrocarbon (PAH) Improvement Plan; The operator shall submit a written plan, to the Environment Agency (the regulator) for approval, of the measures to be taken to minimise PAH emissions (IARC Group 1, 2a & 2b), particularly the marker PAH; Benzo [a] Pyrene (B[a]P) and Volatile Organic Compounds as fugitive releases from existing Appleby and Dawes Lane coke oven battery plants	Permit systems and economic instruments: IPPC permits	Start:	2012	Source affected:	Industry including heat and power production	An improvement condition on the Scunthorpe site permit BL3838IW V007 9 May 2012. The measures described in column 1 of this table (Measure codes); Appleby Coke Ovens 1 -20 and Dawes Lane 1-11 are from the PAH improvement Plan. This PAH Improvement Plan forms part of a wider Coke Oven Battery Recovery Project.
			Expected end:	2024			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Unknown, Operator information			
Indicator:	Reduction in ambient B[a]P concentration						
Target emissions reduction:	Not available						

2	PAH measurement and analysis; The operator undertakes B[a]P monitoring to AURN monitoring location standards with time resolution as low as 1 day. PAH measurements at two locations, using pollution rose analysis to identify key sources. Emission factors to be calculated.	Permit systems and economic instruments: IPPC permits	Start:	2012	Source affected:	Industry including heat and power production	Measurements and analysis indicate that the coke ovens at Appleby and Dawes Lane are the key sources for this exceedance situation. Emission factors calculated for each plant by reverse modelling methodology (Measure No. 4).
			Expected end:	None			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Unknown, Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						

3	Emission measurements; Direct emissions measurements using flameproof blanket fixed over oven doors to create a chimney. Bespoke monitoring to establish improved emission factors.	Permit systems and economic instruments: IPPC permits	Start:	2007	Source affected:	Industry including heat and power production	COMPLETED: Analysis indicates that B[a]P emission dominated by door leakage (>98% of total). Emission rates consistent with estimates at other similar plants across Europe
			Expected end:	2008			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Unknown, Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						

4	Reverse Dispersion Modelling; To provide an independent estimate of emission rates, based on ambient measurements	Permit systems and economic instruments: IPPC permits	Start:	2014	Source affected:	Industry including heat and power production	COMPLETED: Results reasonably consistent with emissions estimates from direct measurements. Indicates that coke ovens are the main source.
			Expected end:	2015			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Unknown, Operator information			
Indicator:	Not available						
			Target emissions reduction:	Not available			

Appleby Coke Ovens 01	Replacement of Door seals; Regular door maintenance is necessary to ensure the maintenance of good seals and a programme to overhaul doors on a daily basis is ongoing	Permit systems and economic instruments: IPPC permits	Start:	2012	Source affected:	Industry including heat and power production	20 seals changed on No.1/2 batteries, 33 seals changed on No.3/4 batteries. Along with seal changes, 158 doors were repaired and 1 frame has been replaced.
			Expected end:	Ongoing			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available	2015 Update - Looking to take doors off the battery bench level and take to dedicated repair facility in 2016. 2016 Plan - All battery 3 doors to be replaced.					
Target emissions reduction:	Not available						

Appleby Coke Ovens 02	Door extractor adjustments; New door extractor as a trial to increase flexibility in door adjustments. Once the optimum position for each door has been ascertained then sealing each individual door will become easier and more consistent	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	New door extractor fitted to 1 Pusher and successful in removing play in seal alignment. Order being progressed for a further two complete extractors assemblies for No. 3 and No. 4 Pusher Machines.
			Expected end:	2016			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available	2015 Update - Repairs carried out to 3 and 4 pusher machines to allow new extractors to be installed. 2016 Plan – New extractors to be installed.					
Target emissions reduction:	Not available						

Appleby Coke Ovens 03	Machine alignments; The development of a cross-battery interlock system, using lasers to accurately line up pusher and coke machines, is under consideration.	Permit systems and economic instruments: IPPC permits	Start:	2015	Source affected:	Industry including heat and power production	Trial complete based on other coke plant system. Scheme is developed, interlock to implement and capital expenditure plan approved. To complete by end 2016.
			Expected end:	2016			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available	2015 Update – Order placed and work commenced on site Aug 2015. Est completion Sept 2016.					
Target emissions reduction:	Not available						

Appleby Coke Ovens 04	Access to carry out door maintenance; There are issues with working at height on the battery bench level to manually plug leaks. Very constrained in meeting Health and Safety requirements as the design is a shallow concrete foundation bench.	Permit systems and economic instruments: IPPC permits	Start:	2012	Source affected:	Industry including heat and power production	4 new EZ bonding lines in place. These will allow for quicker access. Trial of new bench handrail not a success. An alternative option and design developed to implement on the Pusher side; a lanyard and running rail system.
			Expected end:	2016			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Not available			
Indicator:	Not available	2015 Update – Trial successful full engineering design developed - to install 2016. 2016 Plan – Additional improvements to allow quicker and safer bench access through the development of post holes drilled in to the bench to allow full height fencing to be utilised.					
Target emissions reduction:	Not available						

Appleby Coke Ovens 05	New Doors and Frames; Where damage to doors and frames is such that repairs cannot be effected in-situ then a programme of replacement is required. Develop a schedule for door and frame replacement as required at Appleby, subject to the outcome of the capital expenditure plan.	Permit systems and economic instruments: IPPC permits	Start:	2015	Source affected:	Industry including heat and power production	Included in the PAH / coke oven recovery capital expenditure plan. Subject to capital plan. 2015 Update – Approx 21 frames changed according to most recent information. 2016 Update – All damaged frames planned to be changed.
			Expected end:	2024			
			Status:	Planning			
			Spatial scale:	Local			
			Cost:	Unknown, Operator information			
Indicator:	Not available						
			Target emissions reduction:	Not available			

Appleby Coke Ovens 06	New inspection hatch door seals; Inspection hatches are provided in the oven top to allow temperature and visual checks to be made. The hatch seals can become degraded owing to repeated movement and require replacement. A programme of replacements is ongoing, 132 seals are to be replaced.	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	132 hatches fitted , all COMPLETED.
			Expected end:	2015			
			Status:	Implementat ion			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 07	Replacement spigot jointing compound; A seal is provided around the ascension pipe spigot to allow emission-free collection of coke oven gas from each oven.	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	The replacement spigot compound is now being used. Although it is not as reliable (in terms of deterioration) as the compound used in the past, it is better quality than the previously used compound and it is the best available on the market. No further options. Action COMPLETED.
			Expected end:	2014			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 08	Pullman valve replacements; A programme of valve replacements, to combat a design issue, is ongoing.	Permit systems and economic instruments: IPPC permits	Start:	2009	Source affected:	Industry including heat and power production	No, 88, 131, 59 & 46 Pullman Valves replaced this period (Q1 2015). Ongoing replacement. 2015 Update – Approx 17 Pullman Valves replaced according to most recent information. 2016 Plan – Any not fully functional Pullman valves to be changed.
			Expected end:	2015			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operation information			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 09	Tie rod replacements; Periodical surveys are carried out to inspect tie rod integrity and a programme of replacement has commenced and is expected to continue until 2015	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	Tie rod surveys, maintenance and subsequent replacements are carried out on a regular frequency throughout the year.
			Expected end:	Ongoing			
			Status:	Implementat ion			
			Spatial scale:	Local			
			Cost:	Operator Information			
Indicator:	Not available	2015 Update – Approx 17 Pullman Valves replaced according to most recent information. 2016 Plan – Any not fully functional Pullman valves to be changed.					
Target emissions reduction:	Not available						

Appleby Coke Ovens 10	Repairs to battery refractories; A programme of silica welding and end flue repairs to seal oven wall cracks has begun and is expected to continue throughout the remaining operational lifetime of the coke oven plant	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	This is part of the Battery Recovery Programme and PAH capital expenditure plans. Ongoing.
			Expected end:	2024			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information.			
Indicator:	Not available						
Target emissions reduction:	Not available	<p>2015 Update – Approx 14 end flues replaced according to most recent information. New recovery plan put in place Dec 2015. Battery 3 hot idled.</p> <p>2016 Plan – Battery 3 recovery work to be completed. New life extension programme to be implemented.</p>					

Appleby Coke Ovens 11	Replacement of battery refractories; Where repairs to battery refractories are ineffectual or not practically possible, and where the continued operation of the oven will cause excessive emissions, the oven in question is taken out of operation minimising pollution.	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	A significant Battery Recovery Programme has initiated during 2014 and subject to a capital plan proposal put forward. Mainly end wall and flue repairs.
			Expected end:	2024			
			Status:	Planning			
			Spatial scale:	Local			
			Cost:	Subject to Capital plan proposal			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 12	Pressure stabilisation system; A linkage pipe has been placed on either side of the gas booster station, providing a pressure feedback loop.	Permit systems and economic instruments: IPPC permits	Start:	2012	Source affected:	Industry including heat and power production	COMPLETED.
			Expected end:	2013			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 13	New Gas Holder to improve pressure control. Beneficial effects in reducing pressure fluctuations and hence emissions from the batteries caused by high positive pressure.	Permit systems and economic instruments: IPPC permits	Start:	2015	Source affected:	Industry including heat and power production	A scheme to demolish and clear the obsolete gas holder site has been completed. A further capital expenditure scheme for the construction is being developed.
			Expected end:	2017			
			Status:	Planning			
			Spatial scale:	Local			
			Cost:	Operator Information			
Indicator:	Not available	Gas Holder project ongoing. New pressure valve installed, which has resolved pressure spike issue. Ownership of gas holder project is now with Energy Operations.					
Target emissions reduction:	Not available						

Appleby Coke Ovens 14	Underfiring Changeover Timings; Reversal of the heating cycle in the coke ovens at Appleby and Dawes Lane now timed not to coincide	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	COMPLETED.
			Expected end:	2013			
			Status:	Implementat ion			
			Spatial scale:	Local			
			Cost:	Not available			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 15	New benzole plant; The benzole plant will be replaced. This will minimise pressure increase at the batteries, and secondly, the prevent naphthalene in burner flues and leading to cold spots on oven walls, and eventual refractory damage caused by inconsistent heating.	Permit systems and economic instruments: IPPC permits	Start:	2014	Source affected:	Industry including heat and power production	Capital plan approved in 2014. Project is progressing well. Excavations and work on base completed. Construction well underway.
			Expected end:	2016			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						
							2015 Update – Project near completion. 2016 commissioning expected.

Appleby Coke Ovens 16	Coke machine 'inching' facility; The facility to 'inch' the position of the machines will allow better alignment and less damage to the battery metalwork and fabric	Permit systems and economic instruments: IPPC permits	Start:	2015	Source affected:	Industry including heat and power production	New operator panels fitted to all three pushing machines. Systems fitted to four of the six machines. 2015 Update – Trial unsuccessful on pusher machines, implemented on all 3 guide machines in use.
			Expected end:	2016			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 17	Automated leveller control; An automated leveller control system is currently being considered as part of a management of change exercise.	Permit systems and economic instruments: IPPC permits	Start:	2015	Source affected:	Industry including heat and power production	Semi-auto system to be trialled and results of trial ongoing. Can only be fully automated with PLC controls, which is not possible at this time.
			Expected end:	2018			
			Status:	Planning			
			Spatial scale:	Local			
			Cost:	Not available			
Indicator:	Not available						
Target emissions reduction:	Not available	2015 Update – Auto levelling function created and awaiting implementation of machine alignment completion Semi auto facility is available if required.					

Appleby Coke Ovens 18	New venting lids; A new 'venting lid' has been developed to allow burn off of carbon deposits. The build up of carbon deposits on the roof of the oven can also cause pressure issues within the oven by blocking the free passage of coke oven gas leading to door / tops leakage.	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	COMPLETED.
			Expected end:	2013			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 19	Primary cooler replacement; When primary coolers are not effective, the pressure of the by-products plant is increased and this is translated to the batteries and door / tops leakage.	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	All coolers have been replaced in recent years on the by-product plants. COMPLETED. 2015 Update – No. 1 Primary cooler commissioned 2015. Part of new recovery plan stream 2 taken offline Dec 2015 to allow replacement of 6 & 8 primary cooler. 2016 Plan – 6 & 8 primary cooler replacements to be completed. Apply for capital for replacement of no. 7 primary cooler
			Expected end:	2016			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Operator information			
Indicator:	Not available						
Target emissions reduction:	Not available						

Appleby Coke Ovens 20	Heating system checks; The original analysis of waste gas emissions from individual oven flues was completed. This was to information on the operation of each individual oven in terms of heating uniformity and emissions. No benefit from the trial and engaged an external company..	Permit systems and economic instruments: IPPC permits	Start:	2013	Source affected:	Industry including heat and power production	External consultants have completed a heating survey since the initial trials. Additional resources put in place to carry out the recommendations of this survey. Reviewed 6 monthly.
			Expected end:	2024			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:	Not available			
Indicator:	Not available	2015 Update – Extra resource allocated as part of new recovery plan. 2016 Plan – Extra dedicated engineering resource to assist heating team to be allocated.					
Target emissions reduction:	Not available						

Dawes Lane Coke Ovens 01	Closure of Dawes Lane Coke Ovens	Permit systems and economic instruments: other	Start:	2016	Source affected:	Industry including heat and power production	Dawes Lane Coke Ovens closed 8 March 2016
			Expected end:	2016			
			Status:	Implementation			
			Spatial scale:	Local			
			Cost:				
Indicator:							
			Target emissions reduction:				